


F Rating — 3 Hr
T Ratings — 1, 2 & 3 Hr (See Item 2)
L Rating at Ambient — Less Than 1 CFM/sq ft
L Rating at 400 F — 3 CFM/sq ft
W Rating — Class 1



1. **Floor or Wall Assembly** — Min 4-1/2 in. thick reinforced light-weight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified **Concrete Blocks***. Max diam of opening is 6 in. See **Concrete Blocks** (CAZT) category in the Fire Resistance Directory for names of manufacturers.

2. **Sleeves (Optional)** — The following sleeves may be used:

A. **Nonmetallic Sleeve** — Nom 6 in. diam (or smaller) Schedule 40 polyvinyl chloride (PVC) pipe cast or grouted into floor or wall assembly, flush with floor or wall surfaces. **T Rating is 2 Hr when PVC sleeve is used.**

B. **Metallic Sleeve** — Nom 6 in. diam (or smaller) Schedule 40 (or heavier) steel pipe sleeve cast or grouted into floor or wall assembly, flush with floor or wall surfaces. **T Rating is 1 Hr when metallic sleeve is used.**

T Rating is 3 Hr when no sleeve is used.

3. **Firestop System** — The firestop system shall consist of the following:

A. **Packing Material** — Min 3-3/4 in. thickness of min 4.5 pcf mineral wool batt insulation tightly packed into opening as a permanent form. Packing material to be recessed from top surface of floor or from both surfaces of wall as required to accommodate the required thickness of fill material.

B. **Fill, Void or Cavity Material* — Caulk** — Min 1/4 in. thickness of fill material applied within the annulus, flush with the top surface of floor or with both surfaces of wall.

RECTORSEAL — [Metacaulk 835+](#)

*,+ Indicates such products shall bear the UL or cUL Certification Mark for jurisdictions employing the UL or cUL Certification (such as Canada), respectively.

Reprinted from the Online Certifications Directory with permission from UL. ©UL LLC